

**SAMPLE
FRACTION MITIGATION
CONTINGENCY PLAN
FOR DIRECTIONAL DRILLING**

TABLE OF CONTENTS

1.0	Introduction and Purpose	3
2.0	Description of Work	3
3.0	Site Supervisor/Foremen Responsibilities	4
4.0	Equipment	4
5.0	Training	5
6.0	Drilling Procedures	5
6.1	Vac-Truck	6
6.2	Field Response to Frac-Out Occurrence	6
6.3	Response Close-out Procedures	7
6.4	Construction Re-start	7
6.5	Bore Abandonment	7
7.0	Notification	7
7.1	Communicating with Regulatory Agency Personnel	8
7.2	Documentation	8
8.0	Project Completion and Clean-up	8

FRAC-OUT CONTINGENCY PLAN (FCP)

1.0 Introduction and Purpose

Directional bore operations have a potential to release drilling fluids into the surface environment through frac-outs (A frac-out is the condition where drilling mud is released through fractured bedrock into the surrounding rock and sand and travels toward the surface.) Because drilling muds consist largely of a bentonite clay-water mixture, they are not classified as toxic or hazardous substances. However, if it is released into water bodies, bentonite has the potential to adversely impact fish and invertebrates.

While drilling fluid seepage associated with a frac-out is most likely to occur near the bore entry and exit points where the drill head is shallow, frac-outs can occur in any location along a directional bore. This Frac-Out Contingency Plan (FCP) establishes operational procedures and responsibilities for the prevention, containment, and clean-up of frac-outs associated with the proposed directional drilling utility project of _____.

All personnel and Sub-Contractors responsible for the work must adhere to this plan during the directional drilling process.

The specific objectives of this plan are to:

1. Minimize the potential for a frac-out associated with directional drilling activities;
2. Provide for the timely detection of frac-outs;
3. Protect the environmentally sensitive riverbed and associated riparian vegetation;
4. Ensure an organized, timely, and "minimum-impact" response in the event of a frac-out and release of drilling bentonite; and
5. Ensure that all appropriate notifications are made immediately to the customer, management and safety personnel.

2.0 Description of Work:

The proposed project consists of: *(Explain work task in detail to crew members.)*

Drilling operations will be halted by the drill rig operators immediately upon detection of a drop in drilling pressure or other evidence of a frac-out. The clean-up of all spills shall begin immediately. Management & safety department shall be notified immediately of any spills and shall be consulted regarding clean-up procedures. A spill kit shall be on-site and used if a frac-out occurs. A vacuum truck and containment materials, such as straw bales, shall also be on-site prior to and during all operations. The Site Supervisor will be immediately notified. In the event of a frac-out, the on-site foreman/supervisor will conduct an evaluation of the situation and direct recommended mitigation actions, based on the following guidelines:

- a. If the frac-out is minor, easily contained, has not reached the surface and is not threatening sensitive resources, drilling operations may resume after use of a leak stopping compound or redirection of the bore;

- b. If the frac-out has reached the surface, any material contaminated with Bentonite shall be removed by hand to a depth of 2-feet, contained and properly disposed of, as required by law. The drilling contractor shall be responsible for ensuring that the bentonite is either properly disposed of at an approved disposal facility or properly recycled in an approved manner. The Site Supervisor shall notify and take any necessary follow-up response actions in coordination with agency representatives. The Site Supervisor will coordinate the mobilization of equipment stored at off-site locations (e.g., vacuum trucks) on an as needed basis;

3.0 Site Supervisor/Foremen Responsibilities:

The Site Supervisor/Foremen has overall responsibility for implementing this FCP. The Site Supervisor/Foremen will ensure that all employees are trained prior to all drilling. The Site Supervisor/Foremen shall be notified immediately when a frac-out is detected. The Site Supervisor/Foremen will be responsible for ensuring that the safety department is aware of the frac-out, coordinating personnel, response, cleanup, regulatory agency notification and coordination to ensure proper clean-up, disposal of recovered material and timely reporting of the incident. The Site Supervisor/Foremen shall ensure all waste materials are properly containerized, labeled, and removed from the site to an approved disposal facility by personnel experienced in the removal, transport and disposal of drilling mud.

The Site Supervisor/Foremen shall be familiar with all aspects of the drilling activity, the contents of this Frac-out Contingency Plan and the conditions of approval under which the activity is permitted to take place. The Site Supervisor/Foremen shall have the authority to stop work and commit the resources (personnel and equipment) necessary to implement this plan. The Site Supervisor/Foremen shall assure that a copy of this plan is available (onsite) and accessible to all construction personnel. The Site Supervisor/Foremen shall ensure that all workers are properly trained and familiar with the necessary procedures for response to a frac-out, prior to commencement of drilling operations.

4.0 Equipment:

The Site Supervisor shall ensure that:

- All equipment and vehicles are to be checked and maintained daily to prevent leaks of hazardous materials;
- Spill kits and spill containment materials are available on-site at all times and that the equipment is in good working order;
- Equipment required to contain and clean up a frac-out release will either be available at the work site or readily available at an offsite location within 15-minutes of the bore site; and
- If equipment is required to be operated near a riverbed, absorbent pads and plastic sheeting for placement beneath motorized equipment shall be used to protect the riverbed from engine fluids;

5.0 Training

Prior to the start of construction, the Site Supervisor/Foremen, shall ensure that the crew members receive training in the following:

- The provisions of the Frac-out Contingency Plan, equipment maintenance and site specific permit and monitoring requirements;
- Inspection procedures for release prevention and containment equipment and materials;
- Contractor/crew obligation to immediately stop the drilling operation upon first evidence of the occurrence of a frac-out and to immediately report any frac-out releases;
- Contractor/crew member responsibilities in the event of a release;
- Operation of release prevention and control equipment and the location of release control materials, as necessary and appropriate; and
- Protocols for communication with agency representatives who might be on-site during the clean-up effort.

6.0 Drilling Procedures

The following procedures shall be followed each day, prior to the start of work. The Frac-out Contingency Plan shall be available on-site during all construction. The Site Supervisor/Foremen shall be on-site at any time that drilling is occurring or is planned to occur. The Site Supervisor/Foremen shall ensure that a Job Briefing meeting is held at the start of each day of drilling to review the appropriate procedures to be followed in case of a frac-out. Questions shall be answered and clarification given on any point over which the drilling crew or other project staff has concerns.

Drilling pressures shall be closely monitored so they do not exceed those needed to penetrate the formation. Pressure levels shall be monitored randomly by the operator. Pressure levels shall be set at a minimum level to prevent frac-outs. During the pilot bore, maintain the drilled annulus. Cutters and reamers will be pulled back into previously-drilled sections after each new joint of pipe is added.

Exit and entry pits shall be enclosed by silt fences and straw. A spill kit shall be on-site and used if a frac-out occurs. A vacuum truck shall be readily available on-site prior to and during all drilling operations. Containment materials (Straw, silt fencing, sand bags, frac-out spill kits, etc.) shall be staged on-site at location where they are readily available and easily mobilized for immediate use in the event of an accidental release of drilling mud (frac-out). If necessary, barriers (straw bales or sedimentation fences) between the bore site and the edge of the water source, shall be constructed, prior to drilling, to prevent released bentonite material from reaching the water.

Once the drill rig is in place, and drilling begins, the drill operator shall stop work whenever the pressure in the drill rig drops, or there is a lack of returns in the entrance pit. At this time the Site Supervisor/Foremen shall be informed of the potential frac-out. The Site Supervisor/Foremen and the drill rig operator(s) shall work to coordinate the likely location of the frac-out. The location of the frac-out shall be recorded and notes made on the location and measures taken to address the concern. The following subsections shall be adhered to when addressing a frac-out situation.

Water containing mud, silt, bentonite, or other pollutants from equipment washing or other activities, shall not be allowed to enter a lake, flowing stream or any other water source. The Bentonite used in the drilling process shall be either disposed of at an approved disposal facility or recycled in an approved manner. Other construction materials and wastes shall be recycled, or disposed of, as appropriate.

6.1 Vac-Truck:

A vacuum truck shall be staged at a location from which it can be mobilized and relocated so that any place along the drill shot, can be reached by the apparatus, within 10 minutes of a frac-out.

6.2 Field Response to Frac-out Occurrence:

The response of the field crew to a frac-out release shall be immediate and in accordance with procedures identified in this Plan. All appropriate emergency actions that do not pose additional threats to sensitive resources will be taken, as follows:

- a. Directional boring will stop immediately;
- b. The bore stem will be pulled back to relieve pressure on frac-out;
- c. The Site Supervisor/Foremen will be notified to ensure that management and the safety department is notified, adequate response actions are taken and notifications made;
- d. The Site Supervisor/Foremen shall evaluate the situation and recommend the type and level of response warranted, including the level of notification required;
- e. If the frac-out is minor, easily contained, has not reached the surface and is not threatening sensitive resources, a leak stopping compound shall be used to block the frac-out. If the use of leak stopping compound is not fully successful, the bore stem shall be redirected to a new location along the desired drill path where a frac-out has not occurred;
- f. If the frac-out has reached the surface, any material contaminated with Bentonite shall be removed by hand, to a depth of 2-feet, contained and properly disposed of, as required by law. A dike or berm may be constructed around the frac-out to entrap released drilling fluid, if necessary. Clean sand shall be placed and the area returned to pre-project contours; and
- g. If a frac-out occurs, reaches the surface and becomes widespread, the Site Supervisor/Foremen shall authorize a readily accessible vacuum truck and bulldozer stored off-site to be mobilized. The vacuum truck may be either positioned at either end of the line of the drill so that the frac-out can be reached by crews on foot, or may be pulled by a bulldozer, so that contaminated soils can be vacuumed up.

6.3 Response Close-out Procedures:

When the release has been contained and cleaned up, response closeout activities will be conducted at the direction of the Site Supervisor/Foremen and shall include the following:

- a. The recovered drilling fluid will either be recycled or hauled to an approved facility for disposal. No recovered drilling fluids will be discharged into streams, storm drains or any other water source;
- b. All frac-out excavation and clean-up sites will be returned to pre-project contours using clean fill, as necessary; and
- c. All containment measures (fiber rolls, straw bale, etc.) will be removed, unless otherwise specified by the Site Supervisor/Foremen.

6.4 Construction Re-start:

For small releases not requiring external notification, drilling may continue, if 100 percent containment is achieved through the use of a leak stopping compound or redirection of the bore and the clean-up crew remains at the frac-out location throughout the construction period.

For releases requiring external notification and/or other agencies, construction activities will not restart without prior approval from the safety department.

6.5 Bore Abandonment:

Abandonment of the bore will only be required when all efforts to control the frac-out within the existing directional bore have failed.

7.0 Notification:

In the event of a Frac-out that reaches a water source, the Site Supervisor/Foremen will notify safety department so they can notify the appropriate resource agencies. All agency notifications will occur within 24 hours and proper documentation will be accomplished in a timely and complete manner. The following information will be provided:

1. Name and telephone number of person reporting;
2. Location of the release;
3. Date and time of release;
4. Type and quantity, estimated size of release;
5. How the release occurred;
6. The type of activity that was occurring around the area of the frac-out;
7. Description of any sensitive areas, and their location in relation to the frac-out;
8. Description of the methods used to clean up or secure the site; and
9. Listing of the current permits obtained for the project.

7.1 Communicating with Regulatory Agency Personnel:

All employees and subcontractors will adhere to the following protocols when permitting Regulatory Agency Personnel arrive on site. Regulatory Agency Personnel will be required to comply with appropriate safety rules. Only the Site Supervisor/Foremen and the safety department are to coordinate communication with Regulatory Agency Personnel.

7.2 Documentation:

The Site Supervisor/Foremen shall record the frac-out event in his or her daily log. The log will include the following: Details on the release event, including an estimate of the amount of bentonite released, the location and time of release, the size of the area impacted, and the success of the clean-up action. The log report shall also include the: Name and telephone number of person reporting; Date, How the release occurred; The type of activity that was occurring around the area of the free-out: Description of any sensitive areas, and their location in relation to the frac-out: Description of the methods used to clean up or secure the site; and a listing of the current permits obtained for the project.

8.0 Project Completion and Clean-up:

- a. All materials and any rubbish-construction debris shall be removed from the construction zone at the end of each workday;
- b. Sump pits at bore entry and exits will be filled and returned to natural grade; and
- c. All protective measures (fiber rolls, straw bale, silt fence, etc.) will be removed unless otherwise specified by the Site Supervisor/Foremen.

Guidelines For A Successful Directional Crossing Bid Package

The Directional Crossing Contractors Association (DCCA) has been addressing the issue of what information should be made available to contractors and engineers so that future projects proceed as planned. Crossings of rivers and other obstacles using directional drilling techniques are increasingly being utilized around the world. As in any construction project, it is necessary for the contractor to have as much information as possible to prepare a competitive and comprehensive proposal and to be able to successfully install the crossing. Better preconstruction information also allows the work to be undertaken more safely and with less environmental disturbance.

A. DEVELOPMENT AND USES - Originally used in the 1970s, directional crossings are a marriage of conventional road boring and directional drilling of oil wells. The method is now the preferred method of construction. Crossings have been installed for pipelines carrying oil, natural gas, petrochemicals, water, sewerage and other products. Ducts have been installed to carry electric and fiber optic cables. Besides crossing under rivers and waterways, installations have been made crossing under highways, railroads, airport runways, shore approaches, islands, areas congested with buildings, pipeline corridors and future water channels.

B. TECHNOLOGY LIMITS -The longest crossing to date has been about 6,000 ft. Pipe diameters of up to 48 in. have been installed. Although directional drilling was originally used primarily in the U.S. Gulf Coast through alluvial soils, more and more crossings are being undertaken through gravel, cobble, glacial till and hard rock.

C. ADVANTAGES - Directional crossings have the least environmental impact of any alternate method. The technology also offers maximum depth of cover under the obstacle thereby, affording maximum protection and minimizing maintenance costs. River traffic is not interrupted, as most of the work is confined to either bank. Directional crossings have a predictable and short construction schedule. Perhaps most significant, directional crossings are in many cases less expensive than other methods.

D. TECHNIQUE


1. Pilot Hole - A pilot hole is drilled beginning at a prescribed angle from horizontal and continues under and across the obstacle along a design profile made up of straight tangents and long radius arcs. A schematic of the technique is shown in Figure 1. Concurrent to drilling pilot hole, the contractor may elect to run a larger diameter "wash pipe" that will encase the pilot drill string. The wash pipe acts as a conductor casing providing rigidity to the smaller diameter pilot drill string and will also save the drilled hole should it be necessary to retract the pilot string for bit changes. The directional control is brought about by a small bend in the drill string just behind the cutting head. The pilot drill string is not rotated except to orient the bend. If the bend is oriented to the right, the drill path then proceeds in a smooth radius bend to the right. The drill path is monitored by an electronic package housed in the pilot drill string near the cutting head. The electronic package detects the relation of the drill string to the earth's magnetic field and its

inclination. This data is transmitted back to the surface where calculations are made as to the location of the cutting head. Surface location of the drill head also can be used where there is reasonable access.

2. Preream - Once the pilot hole is complete, the hole must be enlarged to a suitable diameter for the product pipeline. For instance, if the pipeline to be installed is 36 in. diameter, the hole may be enlarged to 48 in. diameter or larger. This is accomplished by "prereaming" the hole to successively larger diameters. Generally, the reamer is attached to the drill string on the bank opposite the drilling rig and pulled back into the pilot hole. Joints of drill pipe are added as the reamer makes its way back to the drilling rig. Large quantities of slurry are pumped into the hole to maintain the integrity of the hole and to flush out cuttings.

3. Pullback - Once the drilled hole is enlarged, the product pipeline can be pulled through it. The pipeline is prefabricated on the bank opposite the drilling rig. A reamer is attached to the drill string, and then connected to the pipeline pullhead via a swivel. The swivel prevents any translation of the reamer's rotation into the pipeline string allowing for a smooth pull into the drilled hole. The drilling rig then begins the pullback operation, rotating and pulling on the drill string and once again circulating high volumes of drilling slurry. The pullback continues until the reamer and pipeline break ground at the drilling rig.


Figure 1. Technique




A. ACCESS - Heavy equipment is required on both sides of the crossing. To minimize cost, access to either side of the crossing should be provided with the least distance from an improved road. Often the pipeline right-of-way is used for access. All access agreements should be provided by the owner. It is not practical to negotiate such agreements during the bid process.

B. WORK SPACE

1. Rig Side -The rig spread requires a minimum 100-ft. wide by 150-ft. long area. This area should extend from the entry point away from the crossing, although the entry point should be at least 10 ft inside the prescribed area. Since many components of the rig spread have no predetermined position, the rig site can be made up of smaller irregular areas. Operations are facilitated if the area is level, hardstanding and clear of overhead obstructions. The drilling operation requires large volumes of water for the mixing of the drilling slurry. A nearby source of water is necessary (Figure 2).



2. Pipe Side - Strong consideration should be given to provide a sufficient length of work space to fabricate the product pipeline into one string. The width will be as necessary for normal pipeline construction although a work space of 100-ft. wide by 150-ft. long should be provided at the exit point itself. The length will assure that during the pullback the pipe can be installed in one uninterrupted operation. Tie-ins of successive strings during the pullback operation increase the risk considerably because the pullback should be continuous (Figure 3).



C. PROFILE SURVEY - Once the work locations have been chosen, the area should be surveyed and detailed drawings prepared. The eventual accuracy of the drill profile and alignment is dependent on the accuracy of the survey information.

D. PROFILE DESIGN PARAMETERS

1. Depth of Cover - Once the crossing profile has been taken and the geotechnical investigation complete, a determination of the depth of cover under the crossing is made. Factors considered may include flow characteristics of the river, the depth of scour from periodic flooding, future channel widening/deepening, and the existence of existing pipeline or cable crossings at the location. It is normally recommended that the minimum depth of cover be 20 ft. under the lowest section of the crossing. While 20 ft. is a recommended depth of cover on a river crossing, crossings of other obstacles may have differing requirements.

2. Penetration Angles and Radius of Curvature - An entry angle between 8 and 20 can be used for most crossings. It is preferable that straight tangent sections are drilled before the introduction of a long radius curve. The radius of the curve is determined by the bending characteristic of the product pipeline, increasing with the diameter. A general "rule-of-thumb" for the radius of curvature is 100 ft./1-in. diameter for steel line pipe. The curve usually brings the profile to the elevation providing the design cover of the pipeline under the river. Long horizontal runs can be made at this elevation before curving up towards the exit point. Exit angle should be kept between 5 and 12 to facilitate handling of the product pipeline during pullback.

E. DRILL SURVEY - Most downhole survey tools are electronic devices that give a magnetic azimuth (for "right/left" control) and inclination (for "up/down" control). Surface locators can also be used in conjunction with the downhole electronic package.

1. Accuracy - The accuracy of the drill profile is largely dependent on variations in the earth's magnetic field. For instance, large steel structures (bridges, pilings, other pipelines, etc.) and electric power transmission lines affect magnetic field readings. However, a reasonable drill

target at the pilot hole exit location is 10 ft. left or right, and -10 ft. to +30 ft. in length.

2. As-Built Drawings - Normally, survey calculations are conducted every 30 ft. during pilot hole operations. As-built drawings that are based on these calculations should be provided by the contractor. Alternate methods such as gyroscoping, ground penetrating radar or "intelligent" pigs may also be used to determine the as-built position.

A. NUMBER OF BORINGS - The number of exploration holes is a function of the proposed crossing length and the complexity of the strata. If the crossing is about 1,000 ft. a bore hole made on each side of the crossing may suffice. If an examination of these borings indicates that conditions are likely to be homogeneous on both sides, it may not be necessary to conduct further sampling. If the report indicates anomalies discontinuity in the strata, the presence of rock or large concentrations of gravel it is advisable to make additional borings to better define the strata. Longer crossings (especially large diameter pipelines) that indicate gravel, cobble, boulders or rock should have samples taken about 600-800 ft. apart unless significant anomalies are identified that might necessitate more borings. All borings should be located on the crossing profile along with their surface elevations being properly identified. If possible the borings should be conducted at least 25 ft. off of the proposed centerline. The bore holes should be grouted upon completion. This will help prevent the loss of drilling slurry during the crossing installation.

B. DEPTH OF BORINGS - All borings should be made to a minimum depth of 40 ft. below the lowest point in the crossing or 20 ft. below the proposed depth of the crossing, whichever is greater. In some instances, it may be beneficial to the owner and the contractor to install the crossing at a greater depth than the owner requires for his permit. It is suggested that all borings be through the same elevation to better determine the consistency of the underlying material and note any patterns which may be present.

C. STANDARD CLASSIFICATION OF SOILS - A qualified technician or geologist should classify the material in accordance with the Unified Soil Classification System and ASTM Designations D-2487 and D-2488. It is beneficial to have a copy of the field drilling log completed by the field technician or driller. These logs include visual classifications of materials as well as the driller's interpretation of the subsurface conditions between samples.

D. STANDARD PENETRATION TEST (SPT) - In order to better define the density of granular materials the geotechnical engineer generally uses the Standard Penetration Test (SPT), in general accordance with ASTM Specifications D-1586. This is a field test that involves driving a 2-in. split spoon sampler into the soil by dropping a hammer of a specific weight (usually 140 lb) a specified distance (usually 30 in.) to determine the number of blows necessary to drive the sampler 12 in. In very dense soils, the field technician may note the number of blows required to drive the sampler less than the required 12 in. (i.e., 50 blows for 3 in.). The number obtained is the standard penetration resistance value (N) and is used to estimate the in situ relative density of cohesionless soils. Some geotechnical firms will conduct these penetration tests in cohesive materials and rock, and to a lesser extent, the consistency of cohesive soils and the hardness of rock can be determined.

E. THINWALLED "SHELBY" TUBE SAMPLING - Most geotechnical firms prefer to use a

Thinwalled Tube Sampling method for obtaining samples of cohesive materials. These tests are conducted in general accordance with ASTM Specification D-1587. This test is similar to the Standard Penetration test except the sample is collected by hydraulically pushing a thin-walled seamless steel tube with a sharp cutting edge into the ground. The hydraulic pressure required to collect the sample is noted on the field log. This produces a relatively undisturbed sample that can be further analyzed in the laboratory. These samples can be field tested with handheld penetrometers, but more accurate readings of density and consistency can be obtained by performing unconfined compressive strength tests where the results are noted in tons per square foot. Generally, for directional drilling contractors a standard penetration test using the split spoon sampler described above will suffice in both materials.

F. SIEVE ANALYSIS OF GRANULAR MATERIALS - A sieve analysis is a mechanical test of granular materials performed on samples collected in the field during the standard penetration test with the split spoon sampler. The split spoon samples are taken to the laboratory and processed through a series of screens. The sample provides a percentage analysis of the granular material by size and weight. It is one of the most important tests undertaken.

G. ROCK INFORMATION - If rock is encountered during the soils investigation borings, it is important to determine the type, the relative hardness and the unconfined compressive strength. This information is typically collected by the geotechnical drilling firm by core drilling with a diamond bit core barrel. The typical core sample recovered with this process has a 2-in. diameter. The type of rock is classified by a geologist. The geologist should provide the Rock Quality Designation (RQD) which rates the quality of the rock based on the length of core retrieved in relation to the total length of the core. The hardness of the rock (Mohs' Scale of Hardness) is determined by comparing the rock to ten materials of known hardness. The compressive strength is determined by accurately measuring the core and then compressing the core to failure. This information pertaining to the underlying rock formation is imperative to determine the type of downhole equipment required and the penetration rates that can be expected.

A. WALL THICKNESS -D/T "RULE OF THUMB" - The following table provides generalized recommendations for the selection of steel pipe wall thicknesses relative to pipe diameter. These recommendations are meant to be used only as a starting point in the design. It is recommended that in the final design, specific stresses be calculated and compared with allowable limits.

Diameter (D)	Wall Thickness (t)
6 in. and smaller	0.250 in.
6 to 12 in.	0.375 in.
12 to 30 in.	0.500 in.

For 30 in and larger, $D/t \leq 50$

(For high-density polyethylene (HDPE) pipe, a standard dimension ratio of D/t, SDR, of 11 or less is recommended and the pipe manufacturer should be consulted).

B. STRESS ANALYSIS - In finalizing the design, the stresses imposed during construction and in-service must be calculated and checked to be within allowable limits for the grade of material. The stresses at each stage must be considered acting individually and in combination. Stresses result due to spanning between rollers prior to pullback, the hydrostatic testing pressures, pulling forces during installation, radius of curvature as the pipe enters the ground, the drilling profile curvature, external pressures in the drilled hole, and the working pressure.

1. Pre-installation

- a.** Hoop and longitudinal stresses resulting from hydrostatic testing are calculated.
- b.** Using the known distance between rollers as the free spanning distance, the maximum hogging and sagging moments can be calculated. Considering the greater of these two moments, the maximum spanning stress is calculated. Note: during hydrostatic testing the pipeline will be full of water therefore the additional weight of water must be included in these calculations.

2. Installation

- a.** The spanning stresses calculated in stage 1.b. also apply in this installation phase.
- b.** The theoretical pulling force must be determined in order to provide the stresses that will result. An assumed downhole friction factor of 1.0 is recommended to provide conservative results and to include the effect of the pipeline being pulled around a curve. The maximum predicted pulling force should then be used in calculating the resulting longitudinal stress.
- c.** Allowing for a 10% drilling tolerance, leads to the use of a radius of curvature 90% of the design radius when calculating the longitudinal curvature stresses.
- d.** External pressure from static head in the drilled hole and/or overburden pressures must be considered. It is recommended that the static head resulting from the maximum envisaged drilling fluid density should be used with a factor of safety of 1.5 to provide conservative estimations of resulting hoop and longitudinal stresses.

3. Post-installation

- **a.** The longitudinal curvature stresses calculated for stage 2.c. above are used again here.
- **b.** External pressure stresses from 2.d. apply.
- **c.** Hoop and longitudinal stresses resulting from the final hydrostatic test are calculated.

4. In-service

- **a.** Curvature -see 2.c.
- **b.** External pressure -see 2.d.
- **c.** The maximum working pressure of the pipeline is used in calculating longitudinal and hoop stresses that will be imposed during service.

C. ALLOWABLE STRESSES - Having determined the individual and combined stresses at each stage of construction and those for the in-service condition, they must be compared with allowable limits.

1. ASME B31.8 -1992, Table A842.22 provides the following limits:
 - Maximum allowable longitudinal stress: 80% SMYS.
 - Maximum allowable hoop stress: 72% SMYS.
 - Maximum allowable combined stress: 90% SMYS. (Where SMYS is the Specified Minimum Yield Strength of the pipe material).
2. Regulatory bodies may impose additional limits to those specified above - owner companies should identify any such further constraints and ensure the adequacy of the design.

A. INTRODUCTION - Coatings are applied to provide a corrosion barrier and an abrasion barrier. Directional crossings generally encounter varying materials and often can be exposed to extra abrasion during the pullback. An outer abrasion resistant overcoat is often warranted. To facilitate the pullback of the pipeline the coating should bond well to the pipe to resist soil stresses and have a smooth, hard surface to reduce friction and maintain the corrosion barrier. As in any pipeline construction, the recommended external coating system should be compatible with any specifications for the field joint coating or any internal coating.

B. PIPE COATING - The recommended pipe coating is mill applied fusion bonded epoxy (FBE). The recommended minimum thickness is 20 mils.

C. JOINT COATING - The coating application of the weld area is the most critical field operation to maintain a smooth abrasion-resistant pipe string. It is recommended that the girth weld be coated with FBE powder utilizing the induction heating coil and powder application machine to a minimum dry film thickness of 25 mils. As an alternate, two component catalyzed liquid epoxy may be applied to the girth weld area to a minimum dry film thickness of 25 mils using a paint brush or roller. Tape should never be used for joint coating on the pullback portion of a directional crossing.

D. COATING REPAIR - It is recommended that small coating damaged areas be repaired with a polymeric melt stick patching material. Holidays larger than 1 in. in diameter should be repaired utilizing the two component catalyzed liquid epoxy applied with a paint brush or roller. Tapes should never be used for repair of coating damaged areas on the pullback portion of a directional crossing.

E. ABRASION RESISTANT OVERCOAT - As an extra abrasion resistant barrier for crossings that may encounter stones, boulders or solid rock it is recommended the FBE coated pipeline be overcoated with an epoxy-based polymer concrete. The material should be applied at a mill or with a portable yard coating machine to a minimum thickness of 40 mils. Girth weld and coating damaged areas should be field coated using an epoxy-based polymer concrete compatible with the overcoat material. The patch material should be applied so the material tapers uniformly and feathers into the original coating. Stability of the pipeline in drilled crossings is not normally a concern so a Portland cement type concrete coating is not recommended.

A. BACKGROUND - The directional crossing process requires the use of large volumes of slurry that provide the following functions:

1. Hydraulic cutting with a jet.
2. Provide energy to the drill motor.
3. Lubricate the cutting head.
4. Transport drill cuttings to the surface.
5. Stabilize the hole against collapse.
6. Guard against loss of slurry into surrounding formations.

B. SLURRY COMPOSITION -The slurries most commonly used are bentonite based. Bentonite is a naturally occurring Wyoming clay known for its hydrophilic characteristics. Often polymer extenders are also added to enhance certain characteristics. Material Safety Data Sheets (MSDS) are readily available from suppliers and can be presented to regulatory/disposal authorities.

C. CONTAINMENT - The slurry is pumped downhole and circulates back to the surface and collected in "return pits." These pits typically have a volume of at least 500 cu ft. Depending on the nature of the project, the slurry is pumped from the return pits to a "settling and containment pit." These pits vary in size depending on pumping rates and contain the slurry for recycling or disposal.

D. RECYCLING SLURRY - Slurry that has been circulated downhole and collected in the containment pit is then passed through machinery that separate the cuttings from the slurry. This process involves a series of shaking sieves and various size hydroclones.

E. SLURRY AND CUTTINGS DISPOSAL - Significant amounts of slurry are normally disposed of at the end of a project. Economics for disposal is extremely site specific. This slurry can be disposed of by:

1. Use at another drilling location.
2. Spread onto raw land for water retention improvement.
3. Evacuate to a dump site.

If working in an area of contaminated ground, the slurry should be tested for contamination and disposed of in a manner which meets governmental requirements.

F. COST MITIGATION FOR THE OWNER - With prebid planning and research, the owner can realize significant savings in slurry disposal. It is in the owner's interest to define and specify all disposal issues. In particular:

1. Define an approved disposal site as part of the project specifications.
2. Because it is difficult to estimate disposal quantities, disposal should be a separate bid item as either "cost plus" or on "unit rates."
3. Inadvertent returns are not uncommon and difficult to predict. The issue should be fairly represented to permitting bodies prior to construction. Contingency plans for containment

- and disposal of inadvertent returns should be priced as a separate bid item and agreed prior to construction.

Always utilize a written contract to maximize communication and minimize controversy. A contract should be used to anticipate what the parties intend to do if a problem occurs on the job. The contract should be readable and understandable.

A. The Bid Package - A proposal presented by a contractor to the owner is an offer by the contractor, that becomes a binding contract if accepted by the owner. The parties, price and performance must be specified. Define the project to be undertaken by detailing the scope of work and incorporate all plans and specifications from the bid package.

B. DIFFERING GROUND CONDITIONS AND WALKAWAY PROVISION - Owners should accept the responsibility of performing an adequate geotechnical investigation. Despite adequate testing of ground conditions, unknown, unusual, and/or unexpected ground conditions may be encountered. The contract should provide solutions when the project encounters differing ground conditions. The walkaway provision in the contract should entitle the contractor to stop work and walk away from the job without the owner having the right to take over the contractors equipment. The contractor should be entitled to receive compensation for demobilization, lost profits and work performed prior to walkaway. If the project is completed, the contractor should be paid on a cost-plus basis. Assumption of risk of unforeseen ground conditions by the contractor affects the bid price.

C. ENVIRONMENTAL CONCERNS - Before the project begins, address environmental concerns because owners and contractors are included as potentially responsible parties when environmental damages and cleanup costs are assessed. Federal, state and local laws must be evaluated and licensing, permitting and other regulations must be followed. Directional crossings that damage soil or water may cause liability.

1. Turbidity of Water and Inadvertent Returns - As these events are difficult to predict and work stoppage may occur, the contract should offer a mechanism to mutually address and mitigate the problem. Liabilities are generally shared by both the contractor and owner and many times can be insured.

2. Slurry Disposal - Comply with the regulations of the area regarding slurry disposal. Slurry disposal should be referred to in the contract and bid as a separate line item on a cost plus or unit price basis.

D. ALLOCATION OF RISK OF LOSS - Evaluate and allocate risks of loss that may occur during the project. Owners should share the risk of loss rather than shifting all the losses through the indemnification to the contractor because the bid price is directly affected by contingent losses. Insurance may provide coverage by third parties for losses from differing ground conditions or environmental losses.

E. DISPUTE RESOLUTION - Provide for dispute resolution in the event of controversy by

including mediation or arbitration provisions in the contract. Disputes should be resolved in the following order: 1) negotiation, 2) nonbinding mediation through a third party, 3) binding arbitration and lastly, 4) litigation. Determine who should be parties to the resolution, what law will be used and where the dispute will be resolved.

A Contract Law Seminar notebook with recommended model provisions is available from the office of the DCCA.

This booklet was prepared by the Guidelines Committee of Directional Crossing Contractors Association. The Guidelines were adopted by the Association on April 21, 1995. The members of the DCCA Guidelines Committee are:

**Eric Skonberg, Tom Allen, Grady Bell, Herb Fluharty,
Rick Gump, Neil Smith & Tom Wilson**

Copyright © 1995 DCCA