MINOR SITE PLAN FOR MEDWAY COMMONS DECEMBER 22, 2022 N OF MEDWAY PLANNING AND)MTC DEVELOPMENT BOAR APPROVAL DATE: NDORSEMENT DATE


CHIPOTLE & STARBUCKS 67C MAIN STREET MEDWAY, MASSACHUSETTS PARCELS 41-023-067A & B, CENTRAL BUSINESS ZONE LAST REVISED: FEBRUARY 24, 2023

LIST OF DRAWINGS				
SHEET NO.	SHEET TITLE			
	COVER			
1 OF 2	ALTA/NSPS LAND TITLE SURVEY (BY R.E. CAMERON & ASSOCIATES, INC.)			
2 OF 2	ALTA/NSPS LAND TITLE SURVEY (BY R.E. CAMERON & ASSOCIATES, INC.)			
C-100	OVERALL SITE PLAN			
C-101	DEMOLITION PLAN			
C-102	SITE PLAN			
C-103	UTILITY, GRADING, DRAINAGE, & EROSION CONTROL PLAN			
C-104	LANDSCAPE PLAN			
C-105	CIRCULATION PLAN			
C-501	EROSION CONTROL NOTES & DETAILS			
C-502	DETAILS			
C-503	DETAILS			
C-504	DETAILS			
A201	EXISTING ELEVATIONS (BY SCOTT GRIFFIN ARCHITECTS)			
A202	PROPOSED ELEVATIONS (BY SCOTT GRIFFIN ARCHITECTS)			
A203	PROPOSED ELEVATIONS COLORED (BY SCOTT GRIFFIN ARCHITECTS)			
A204	3D PERSPECTIVES (BY SCOTT GRIFFIN ARCHITECTS)			

WAIVER REQUEST:

THE FOLLOWING IS A WAIVER REQUEST FROM THE TOWN OF MEDWAY'S SITE PLAN RULES AND REGULATIONS 1. ARTICLE V SECTION 205-4 - ALL EXISTING AND PROPOSED ELEVATIONS SHALL REFER TO NAVD88

PROJECT NO: C1026-023



PREPARED BY:

Portsmouth, NH 03801 (603) 433-8818

PREPARED FOR: Charter Realty & Development 1666 Massachusetts Ave - Suite 6A Lexington, Massachusetts 02420


PREPARED WITH:

Scott Griffin Architects 880 Main Street 5th Floor Waltham, Massachusetts 02451


LOCATION MAP SCALE: 1" = 2000'


77 Cornorate Drive

PERMIT SET - NOT FOR CONSTRUCTION COMPLETE SET 17 SHEETS









	ighe	880	nd	
Cł	nor si nipot arbu		FOR	
Medway Commons 67C Main Street				
67	C Main		5	
67 Me	-	Street	5	
67 Me Ma	C Main dway, ssachu	Street	5	
67 Me Ma Ch	C Main dway, ssachu arter F	Street		
67 Me Ma	C Main dway, ssachu arter F	Street setts Realty &		
67 Me Ma Ch	C Main dway, ssachu arter F	Street setts Realty &		
67 Me Ma Ch	C Main dway, ssachu arter F velopn	Street setts Realty &	Э.	
670 Me Ma Ch De	C Main dway, ssachu arter F velopn	Street Street Setts Realty & Corp Revise PER Revie Revise PER Revie Revise PER LEASE	D .	
67 Me Ma Ch De	C Main dway, ssachu arter F velopn	Street Isetts Realty & nent Corp Revise PER Revie COMMENTS REVISE PER LEASE DESCRIPTION	D .	
67 Me Ma Ch De Ch De	C Main dway, ssachu arter F velopn 2/24/2023 1/31/2023 1/31/2023 DATE CT NO:	Street Street Setts Realty & nent Corp Revise per revie Revise per revie Revise per revie Description	D . D . W E PLAN C 1026-023 R 22, 2022 BITS.DWG	
67 Me Ma Ch De 2 1 MARK PROJE	C Main dway, ssachu arter F velopn 2/24/2023 1/31/2023 1/31/2023 1/31/2023 CT NO: C1026-018- N BY: CED:	Street Isetts Realty & nent Corp Revise PER REVIE COMMENTS REVISE PER REVIE DESCRIPTION	D.	
67 Me Ma Ma Ch De 2 1 MARK PROJE FILE: DRAW CHECK	C Main dway, ssachu arter F velopn 2/24/2023 1/31/2023 1/31/2023 1/31/2023 CT NO: CT N	Street Isetts Realty & nent Corp Revise PER REVIE COMMENTS REVISE PER REVIE DESCRIPTION	D . D . 	
67 Me Ma Ma Ch De 2 1 MARK PROJE FILE: DRAW CHECK	C Main dway, ssachu arter F velopn 2/24/2023 1/31/2023 1/31/2023 1/31/2023 DATE CINO: CIRCUL	Street St	D. 	

0		4	0'		
	GRAPHIC SCALE				

GENERAL PROJECT INFORMATION PROJECT NAME: MEDWAY COMMONS

PROJECT ADDRESS: 67C MAIN STREET MEDWAY, MASSACHUSETTS PROJECT MAP / LOT: MAP 41 / LOT 23 PROJECT LATITUDE: 42.15682 N PROJECT LONGITUDE: -71.405030 W

PROJECT DESCRIPTION

THE PROJECT CONSISTS OF SITE IMPROVEMENTS AT THE EXISTING STARBUCKS FOR IMPROVED TRAFFIC FLOW AS WELL AS NEW TENANTS IN THE EXISTING MCDONALDS BUILDING. MINOR SITE IMPROVEMENTS INCLUDE RECONFIGURING PARKING, UTILITY IMPROVEMENTS, REVISE CIRCULATION AND IMPROVED LANDSCAPING.

DISTURBED AREA

THE TOTAL AREA TO BE DISTURBED IS APPROXIMATELY 0.25 ACRES.

EROSION CONTROL NOTES:

- ALL EROSION CONTROL MEASURES AND PRACTICES SHALL CONFORM TO THE MOST CURRENT MASSACHUSETTS STORMWATER STANDARDS PREPARED BY THE MADEP.
- PRIOR TO ANY WORK OR SOIL DISTURBANCE, CONTRACTOR SHALL SUBMIT SHOP DRAWINGS FOR EROSION CONTROL MEASURES AS REQUIRED IN THE PROJECT MANUAL CONTRACTOR SHALL INSTALL TEMPORARY EROSION CONTROL BARRIERS, INCLUDING HAY
- BALES, SILT FENCES, MULCH BERMS, SILT SACKS AND SILT SOCKS AS SHOWN IN THESE DRAWINGS AS THE FIRST ORDER OF WORK. SILT SACK INLET PROTECTION SHALL BE INSTALLED IN ALL EXISTING AND PROPOSED CATCH
- BASIN INLETS WITHIN THE WORK LIMITS AND BE MAINTAINED FOR THE DURATION OF THE PR01ECT PERIMETER CONTROLS INCLUDING SILT FENCES, MULCH BERM, SILT SOCK, AND/OR HAY BALE
- BARRIERS SHALL BE MAINTAINED FOR THE DURATION OF THE PROJECT UNTIL NON-PAVED AREAS HAVE BEEN STABILIZED.
- 5. THE CONTRACTOR SHALL REMOVE AND PROPERLY DISPOSE OF ALL TEMPORARY EROSION
- CONTROL DEVICES UPON COMPLETION OF CONSTRUCTION. ALL DISTURBED AREAS NOT OTHERWISE BEING TREATED SHALL RECEIVE 6" LOAM, SEED AND FERTILIZER.
- 3. INSPECT ALL INLET PROTECTION AND PERIMETER CONTROLS WEEKLY AND AFTER EACH RAIN STORM OF 0.25 INCH OR GREATER. REPAIR/MODIFY PROTECTION AS NECESSARY TO MAXIMIZE EFFICIENCY OF FILTER. REPLACE ALL FILTERS WHEN SEDIMENT IS 1/3 THE FILTER HEIGHT.

STABILIZATION:

. AN AREA SHALL BE CONSIDERED STABLE WHEN ONE OF THE FOLLOWING HAS OCCURRED:

- A. BASE COURSE GRAVELS HAVE BEEN INSTALLED IN AREAS TO BE PAVED;
- B. A MINIMUM OF 85% VEGETATED GROWTH HAS BEEN ESTABLISHED; C. A MINIMUM OF 3" OF NON-EROSIVE MATERIAL SUCH AS STONE OR RIPRAP HAS BEEN INSTALLED
- D. EROSION CONTROL BLANKETS HAVE BEEN PROPERLY INSTALLED.;
- E. IN AREAS TO BE PAVED, "STABLE" MEANS THAT BASE COURSE GRAVELS MEETING THE REQUIREMENTS OF MASSDOT STANDARD FOR ROAD AND BRIDGE CONSTRUCTION, 2016, HAVE BEEN INSTALLED.
- WINTER STABILIZATION PRACTICES: A. ALL PROPOSED VEGETATED AREAS THAT DO NOT EXHIBIT A MINIMUM OF 85 PERCENT VEGETATIVE GROWTH BY OCTOBER 15, OR WHICH ARE DISTURBED AFTER OCTOBER 15, SHALL BE STABILIZED BY SEEDING AND INSTALLING EROSION CONTROL BLANKETS ON SLOPES GREATER THAN 3:1, AND SEEDING AND PLACING 3 TO 4 TONS OF MULCH PER ACRE, SECURED WITH ANCHORED NETTING, ELSEWHERE. THE INSTALLATION OF EROSION CONTROL BLANKETS OR MULCH AND NETTING SHALL NOT OCCUR OVER ACCUMULATED SNOW OR ON FROZEN GROUND AND SHALL BE COMPLETED IN ADVANCE OF THAW OR SPRING MELT EVENTS;
- ALL DITCHES OR SWALES WHICH DO NOT EXHIBIT A MINIMUM OF 85 PERCENT VEGETATIVE GROWTH BY OCTOBER 15, OR WHICH ARE DISTURBED AFTER OCTOBER 15, SHALL BE STABILIZED TEMPORARILY WITH STONE OR EROSION CONTROL BLANKETS APPROPRIATE FOR THE DESIGN FLOW CONDITIONS;
- C. AFTER OCTOBER 15, INCOMPLETE ROAD OR PARKING SURFACES, WHERE WORK HAS STOPPED FOR THE WINTER SEASON, SHALL BE PROTECTED WITH A MINIMUM OF 3 INCHES OF CRUSHED GRAVEL PER MASSDOT, OR IF CONSTRUCTION IS TO CONTINUE THROUGH THE WINTER SEASON BE CLEARED OF ANY ACCUMULATED SNOW AFTER EACH STORM EVENT
- STABILIZATION SHALL BE INITIATED ON ALL LOAM STOCKPILES, AND DISTURBED AREAS, WHERE CONSTRUCTION ACTIVITY SHALL NOT OCCUR FOR MORE THAN TWENTY-ONE (21) CALENDAR DAYS BY THE FOURTEENTH (14TH) DAY AFTER CONSTRUCTION ACTIVITY HAS PERMANENTLY OR TEMPORARILY CEASED IN THAT AREA. STABILIZATION MEASURES TO BE USED INCLUDE: A. TEMPORARY SEEDING;
- B. MULCHING.
- ALL AREAS SHALL BE STABILIZED WITHIN 45 DAYS OF INITIAL DISTURBANCE. WHEN CONSTRUCTION ACTIVITY PERMANENTLY OR TEMPORARILY CEASES WITHIN 100 FEET OF NEARBY SURFACE WATERS OR DELINEATED WETLANDS, THE AREA SHALL BE STABILIZED WITHIN SEVEN (7) DAYS OR PRIOR TO A RAIN EVENT. ONCE CONSTRUCTION ACTIVITY CEASES PERMANENTLY IN AN THESE AREAS, SILT FENCES, MULCH BERMS, HAY BALE BARRIERS AND ANY EARTH/DIKES SHALL BE REMOVED ONCE PERMANENT MEASURES ARE
- ESTABLISHED. DURING CONSTRUCTION, RUNOFF WILL BE DIVERTED AROUND THE SITE WITH EARTH DIKES, PIPING OR STABILIZED CHANNELS WHERE POSSIBLE. SHEET RUNOFF FROM THE SITE WILL BE FILTERED THROUGH SILT FENCES, MULCH BERMS, HAY BALE BARRIERS, OR SILT SOCKS. ALL STORM DRAIN BASIN INLETS SHALL BE PROVIDED WITH FLARED END SECTIONS AND TRASH RACKS. THE SITE SHALL BE STABILIZED FOR THE WINTER BY OCTOBER 15.

DUST CONTROL:

- . THE CONTRACTOR SHALL BE RESPONSIBLE TO CONTROL DUST THROUGHOUT THE CONSTRUCTION PERIOD.
- 2. DUST CONTROL METHODS SHALL INCLUDE, BUT BE NOT LIMITED TO SPRINKLING WATER ON EXPOSED AREAS, COVERING LOADED DUMP TRUCKS LEAVING THE SITE, AND TEMPORARY MULCHING.
- DUST CONTROL MEASURES SHALL BE UTILIZED SO AS TO PREVENT THE MIGRATION OF DUST FROM THE SITE TO ABUTTING AREAS.

STOCKPILES:

- LOCATE STOCKPILES A MINIMUM OF 50 FEET AWAY FROM CATCH BASINS, SWALES, AND CULVERTS.
- ALL STOCKPILES SHOULD BE SURROUNDED WITH TEMPORARY EROSION CONTROL MEASURES PRIOR TO THE ONSET OF PRECIPITATION.
- PERIMETER BARRIERS SHOULD BE MAINTAINED AT ALL TIMES, AND ADJUSTED AS NEEDED TO ACCOMMODATE THE DELIVERY AND REMOVAL OF MATERIALS FROM THE STOCKPILE. THE INTEGRITY OF THE BARRIER SHOULD BE INSPECTED AT THE END OF EACH WORKING DAY.
- PROTECT ALL STOCKPILES FROM STORMWATER RUN-OFF USING TEMPORARY EROSION CONTROL MEASURES SUCH AS BERMS, SILT SOCK, OR OTHER APPROVED PRACTICE TO PREVENT MIGRATION OF MATERIAL BEYOND THE IMMEDIATE CONFINES OF THE STOCKPILES.

VEGETATION:

- .. TEMPORARY GRASS COVER:
- A. SEEDBED PREPARATION:
- a. APPLY FERTILIZER AT THE RATE OF 600 POUNDS PER ACRE OF 10-10-10. APPLY LIMESTONE (EQUIVALENT TO 50 PERCENT CALCIUM PLUS MAGNESIUM OXIDE) AT A RATE OF THREE (3) TONS PER ACRE; B. SEEDING:
- a. UTILIZE ANNUAL RYE GRASS AT A RATE OF 40 LBS/ACRE;
- b. WHERE THE SOIL HAS BEEN COMPACTED BY CONSTRUCTION OPERATIONS, LOOSEN SOIL TO A DEPTH OF TWO (2) INCHES BEFORE APPLYING FERTILIZER, LIME AND SEED
- c. APPLY SEED UNIFORMLY BY HAND, CYCLONE SEEDER, OR HYDROSEEDER (SLURRY INCLUDING SEED AND FERTILIZER). HYDROSEEDINGS, WHICH INCLUDE MULCH, MAY

HYDROSEEDING;

- C. MAINTENANCE DAMS, ETC.).
- 2. PERMANENT MEASURES AND PLANTINGS:
- THREE (3) TONS PER ACRE IN ORDER TO PROVIDE A PH VALUE OF 5.5 TO 6.5; B
- FERTILIZER
- C. SOIL CONDITIONERS AND FERTILIZER SHALL BE APPLIED AT THE RECOMMENDED RATES
- SEED SHALL BE SOWN AT THE RATE SHOWN BELOW. SOWING SHALL BE DONE ON A CALM, DRY DAY, PREFERABLY BY MACHINE, BUT IF BY HAND, ONLY BY EXPERIENCED HALF THE SEED SHALL BE SOWN IN ONE DIRECTION AND THE OTHER HALF AT RIGHT POUNDS PER LINEAR FOOT OF WIDTH;
- HAY MULCH SHALL BE APPLIED IMMEDIATELY AFTER SEEDING AS INDICATED ABOVE; F. THE SURFACE SHALL BE WATERED AND KEPT MOIST WITH A FINE SPRAY AS REQUIRED, WITHOUT WASHING AWAY THE SOIL, UNTIL THE GRASS IS WELL ESTABLISHED. ANY
- AND ALL NOXIOUS WEEDS REMOVED; G. THE CONTRACTOR SHALL PROTECT AND MAINTAIN THE SEEDED AREAS UNTIL ACCEPTED;
- H. A GRASS SEED MIXTURE CONTAINING THE FOLLOWING SEED REQUIREMENTS SHALL BE APPLIED AT THE INDICATED RATE:

SEED MIX	F	APPLICATIO
CREEPINC	RED FESCUE	66 LBS
KENTUCK	Y BLUE	36 LBS
PERENNIA	L RYE	6 LBS
REDTOP		6 LBS

IN NO CASE SHALL THE WEED CONTENT EXCEED ONE (1) PERCENT BY WEIGHT. ALL SEED SHALL COMPLY WITH STATE AND FEDERAL SEED LAWS. SEEDING SHALL BE DONE NO LATER THAN SEPTEMBER 15. IN NO CASE SHALL SEEDING TAKE PLACE OVER SNOW.

- 3. DORMANT SEEDING (SEPTEMBER 15 TO FIRST SNOWFALL): A. FOLLOW PERMANENT MEASURES SLOPE, LIME, FERTILIZER AND GRADING
- INDICATED FOR PERMANENT MEASURES.

WASTE DISPOSAL WASTE MATERIAL

- A. ALL WASTE MATERIALS SHALL BE COLLECTED AND STORED IN SECURELY LIDDED RECEPTACLES. ALL TRASH AND CONSTRUCTION DEBRIS FROM THE SITE SHALL BE DEPOSITED IN A DUMPSTER;
- NO CONSTRUCTION WASTE MATERIALS SHALL BE BURIED ON SITE; C. ALL PERSONNEL SHALL BE INSTRUCTED REGARDING THE CORRECT PROCEDURE FOR WASTE DISPOSAL BY THE SUPERINTENDENT.
- 2. HAZARDOUS WASTE: A. ALL HAZARDOUS WASTE MATERIALS SHALL BE DISPOSED OF IN THE MANNER SPECIFIED BY LOCAL OR STATE REGULATION OR BY THE MANUFACTURER;
- B. SITE PERSONNEL SHALL BE INSTRUCTED IN THESE PRACTICES BY THE SUPERINTENDENT. SANITARY WASTE:
- ONCE PER WEEK BY A LICENSED SANITARY WASTE MANAGEMENT CONTRACTOR.

SPILL PREVENTION:

- 1. CONTRACTOR SHALL BE FAMILIAR WITH SPILL PREVENTION MEASURES REQUIRED BY LOCAL, STATE AND FEDERAL AGENCIES. AT A MINIMUM, CONTRACTOR SHALL FOLLOW THE BEST MANAGEMENT SPILL PREVENTION PRACTICES OUTLINED BELOW. THE FOLLOWING ARE THE MATERIAL MANAGEMENT PRACTICES THAT SHALL BE USED TO
- REDUCE THE RISK OF SPILLS OR OTHER ACCIDENTAL EXPOSURE OF MATERIALS AND SUBSTANCES DURING CONSTRUCTION TO STORMWATER RUNOFF: GOOD HOUSEKEEPING - THE FOLLOWING GOOD HOUSEKEEPING PRACTICE SHALL BE
 - FOLLOWED ON SITE DURING CONSTRUCTION: a. ONLY SUFFICIENT AMOUNTS OF PRODUCTS TO DO THE JOB SHALL BE STORED ON
 - b. ALL REGULATED MATERIALS STORED ON SITE SHALL BE STORED IN A NEAT, ORDERLY UNDER A ROOF OR OTHER ENCLOSURE, ON AN IMPERVIOUS SURFACE; MANUFACTURER'S RECOMMENDATIONS FOR PROPER USE AND DISPOSAL SHALL BE
 - FOLLOWED;
 - DISPOSAL OF MATERIALS;
 - THE MANUFACTURER;
 - THE CONTAINER.
 - REGULATED SUBSTANCES.
- B. RISKS ASSOCIATED WITH HAZARDOUS MATERIALS: a. PRODUCTS SHALL BE KEPT IN THEIR ORIGINAL CONTAINERS UNLESS THEY ARE NOT
- RESEALABLE;
- b. ORIGINAL LABELS AND MATERIAL SAFETY DATA SHALL BE RETAINED FOR IMPORTANT **PRODUCT INFORMATION;**
- TO THE MANUFACTURER'S RECOMMENDED METHODS OF DISPOSAL.
- C. PRODUCT SPECIFIC PRACTICES THE FOLLOWING PRODUCT SPECIFIC PRACTICES SHALL **BE FOLLOWED ON SITE:**
- a. PETROLEUM PRODUCTS:
- PREVENTIVE MAINTENANCE TO REDUCE LEAKAGE PETROLEUM PRODUCTS SHALL BE STORED IN TIGHTLY SEALED CONTAINERS WHICH ARE ACCORDING TO THE MANUFACTURER'S RECOMMENDATIONS. b. FERTILIZERS:
- FERTILIZERS USED SHALL BE APPLIED ONLY IN THE MINIMUM AMOUNTS DIRECTED BY THE SPECIFICATIONS;
- ONCE APPLIED FERTILIZERS SHALL BE WORKED INTO THE SOIL TO LIMIT EXPOSURE TO
- STORMWATER: STORAGE SHALL BE IN A COVERED SHED OR ENCLOSED TRAILERS. THE CONTENTS OF ANY PARTIALLY USED BAGS OF FERTILIZER SHALL BE TRANSFERRED TO A SEALABLE PLASTIC BIN TO AVOID SPILLS
- c. PAINTS: • ALL CONTAINERS SHALL BE TIGHTLY SEALED AND STORED WHEN NOT REQUIRED FOR USE;
- EXCESS PAINT SHALL NOT BE DISCHARGED TO THE STORM SEWER SYSTEM;
- INSTRUCTIONS OR STATE AND LOCAL REGULATIONS D. SPILL CONTROL PRACTICES - IN ADDITION TO GOOD HOUSEKEEPING AND MATERIAL
- MANAGEMENT PRACTICES DISCUSSED IN THE PREVIOUS SECTION, THE FOLLOWING PRACTICES SHALL BE FOLLOWED FOR SPILL PREVENTION AND CLEANUP: a. MANUFACTURER'S RECOMMENDED METHODS FOR SPILL CLEANUP SHALL BE CLEARLY

BE LEFT ON SOIL SURFACE. SEEDING RATES MUST BE INCREASED 10% WHEN

a. TEMPORARY SEEDING SHALL BE PERIODICALLY INSPECTED. AT A MINIMUM, 95% OF THE SOIL SURFACE SHOULD BE COVERED BY VEGETATION. IF ANY EVIDENCE OF EROSION OR SEDIMENTATION IS APPARENT, REPAIRS SHALL BE MADE AND OTHER TEMPORARY MEASURES USED IN THE INTERIM (MULCH, FILTER BARRIERS, CHECK

A. LIMESTONE SHALL BE THOROUGHLY INCORPORATED INTO THE LOAM LAYER AT A RATE OF FERTILIZER SHALL BE SPREAD ON THE TOP LAYER OF LOAM AND WORKED INTO THE SURFACE. FERTILIZER APPLICATION RATE SHALL BE 800 POUNDS PER ACRE OF 10-20-20

AND SHALL BE THOROUGHLY WORKED INTO THE LOAM. LOAM SHALL BE RAKED UNTIL THE SURFACE IS FINELY PULVERIZED, SMOOTH AND EVEN, AND THEN COMPACTED TO AN EVEN SURFACE CONFORMING TO THE REQUIRED LINES AND GRADES WITH APPROVED ROLLERS WEIGHING BETWEEN 4-1/2 POUNDS AND 5-1/2 POUNDS PER INCH OF WIDTH; WORKMEN. IMMEDIATELY BEFORE SEEDING, THE SOIL SHALL BE LIGHTLY RAKED. ONE ANGLES TO THE ORIGINAL DIRECTION. IT SHALL BE LIGHTLY RAKED INTO THE SOIL TO A DEPTH NOT OVER 1/4 INCH AND ROLLED WITH A HAND ROLLER WEIGHING NOT OVER 100

AREAS WHICH ARE NOT SATISFACTORILY COVERED WITH GRASS SHALL BE RESEEDED,

ON RAT S/ACRE S/ACRE S/ACRE

S/ACRE

REQUIREMENTS. APPLY SEED MIXTURE AT TWICE THE INDICATED RATE. APPLY MULCH AS

A. ALL SANITARY WASTE SHALL BE COLLECTED FROM THE PORTABLE UNITS A MINIMUM OF

MANNER IN THEIR PROPER (ORIGINAL IF POSSIBLE) CONTAINERS AND, IF POSSIBLE,

d. THE SITE SUPERINTENDENT SHALL INSPECT DAILY TO ENSURE PROPER USE AND

e. SUBSTANCES SHALL NOT BE MIXED WITH ONE ANOTHER UNLESS RECOMMENDED BY

f. WHENEVER POSSIBLE ALL OF A PRODUCT SHALL BE USED UP BEFORE DISPOSING OF

g. THE TRAINING OF ON-SITE EMPLOYEES AND THE ON-SITE POSTING OF RELEASE RESPONSE INFORMATION DESCRIBING WHAT TO DO IN THE EVENT OF A SPILL OF

HAZARDOUS PRODUCTS - THE FOLLOWING PRACTICES SHALL BE USED TO REDUCE THE

c. SURPLUS PRODUCT THAT MUST BE DISPOSED OF SHALL BE DISCARDED ACCORDING

ALL ON SITE VEHICLES SHALL BE MONITORED FOR LEAKS AND RECEIVE REGULAR

CLEARLY LABELED. ANY ASPHALT BASED SUBSTANCES USED ON SITE SHALL BE APPLIED

EXCESS PAINT SHALL BE DISPOSED OF PROPERLY ACCORDING TO MANUFACTURER'S

POSTED AND SITE PERSONNEL SHALL BE MADE AWARE OF THE PROCEDURES AND THE LOCATION OF THE INFORMATION AND CLEANUP SUPPLIES;

- MATERIALS AND EQUIPMENT NECESSARY FOR SPILL CLEANUP SHALL BE KEPT IN THE MATERIAL STORAGE AREA ON SITE. EQUIPMENT AND MATERIALS SHALL INCLUDE BUT NOT BE LIMITED TO BROOMS, DUSTPANS, MOPS, RAGS, GLOVES, GOGGLES, KITTY LITTER, SAND, SAWDUST AND PLASTIC OR METAL TRASH CONTAINERS SPECIFICALLY FOR THIS PURPOSE;
- c. ALL SPILLS SHALL BE CLEANED UP IMMEDIATELY AFTER DISCOVERY; d. THE SPILL AREA SHALL BE KEPT WELL VENTILATED AND PERSONNEL SHALL WEAR APPROPRIATE PROTECTIVE CLOTHING TO PREVENT INJURY FROM CONTACT WITH A HAZARDOUS SUBSTANCE;
- e. SPILLS OF TOXIC OR HAZARDOUS MATERIAL SHALL BE REPORTED TO THE
- APPROPRIATE LOCAL, STATE OR FEDERAL AGENCIES AS REQUIRED; f. THE SITE SUPERINTENDENT RESPONSIBLE FOR DAY-TO-DAY SITE OPERATIONS SHALL BE THE SPILL PREVENTION AND CLEANUP COORDINATOR.
- E. VEHICLE FUELING AND MAINTENANCE PRACTICE: a. CONTRACTOR SHALL MAKE AN EFFORT TO PERFORM EQUIPMENT/VEHICLE FUELING AND MAINTENANCE AT AN OFF-SITE FACILITY;
- b. CONTRACTOR SHALL PROVIDE AN ON-SITE FUELING AND MAINTENANCE AREA THAT IS CLEAN AND DRY;
- c. IF POSSIBLE THE CONTRACTOR SHALL KEEP AREA COVERED
- d. CONTRACTOR SHALL KEEP A SPILL KIT AT THE FUELING AND MAINTENANCE AREA;
- e. CONTRACTOR SHALL REGULARLY INSPECT VEHICLES FOR LEAKS AND DAMAGE; CONTRACTOR SHALL USE DRIP PANS, DRIP CLOTHS, OR ABSORBENT PADS WHEN
- REPLACING SPENT FLUID.

EROSION CONTROL OBSERVATIONS AND MAINTENANCE PRACTICES THIS PROJECT DOES NOT EXCEED ONE (1) ACRE OF DISTURBANCE AND THEREFORE DOES NOT REQUIRES A SWPPP.

